Item No.	Description of work	Per	Rate	Quantity
			Rs. a. p.	
5(a)	Size stone in surki mortar for core wall at breach	C.ft.	0 5 0	480
(b)	Puddle wall at the breach site	,,	0 12 0	41
6	Constructing rough stone revetment at the breach	,,	2 8 0	83
7	Turfing the slopes of bund both slopes	Sqr.	0 12 0	202
8	Watering and consolidation charges for the available earth used to bund	C.yd.	0 2 6	3,025
9	Providing and fixing grade stones including, figuring, painting, etc.	Each	2 8 0	5
10	Do Index stones	,,	1 0 0	5
11	Do B.M. stones	,,	4 0 0	2
12	Do Register No. and date stone	,,	10 0 0	1
13	Providing iron gauge plates one at the sluice and the other at weir	,,	10 0 0	2
	SILT CLEARING IN THE TANK BED.			
1	Removal of silt from the tank bed	C.yd.	0 3 0	2,963
	CONSTRUCTING A MASONRY WEIR 33 FT. LONG AT R.L. 50·00.			
1	Earthwork excavation in hard gravelly soil and using it to bund	C.yd.	0 4 0	178
2	Earthwork excavation in ordinary soil	,,	0 3 6	92
3	Cement concrete 1 : 4 : 8 foundation of body wall	C.ft.	0 7 0	146
4	Size stone in cement mortar 1 : 5	,,	0 8 0	275
5	Cement plastering	Sqr.	8 8 0	1·00
6	Cement pointing to exposed masonry	,,	4 0 0	1·50
7	Rough stone work new	C.yd.	2 8 0	76
8	Jungle clearing	S.yd.	0 0 1½	889
9	Unforeseen works	L. S.		
	SLUICE AT R.L. 38·00.			
1	Cutting open the bund and refilling with watering and consolidation	C.yd.	0 6 0	107
2	Earthwork excavating foundation	,,	0 4 0	10
3	Stone jelly concrete in cement mortar	C.ft.	0 7 0	136
4	Size stone in cement mortar	,,	0 7 0	641
5	Stone jelly concrete in cement mortar 1 : 2 : 4	C.ft.	1 0 0	38
6	Cement pointing 1 : 3	Sqr.	4 0 0	1·50
7	Cement plastering 1 : 3 for cistern bed	,,	8 8 0	0·50
8	Providing 6″ diar. C.I. pipes of 12′ long from Bhadravati	Each	20 0 0	5
9	Carting the pipes to site in 3 carts from Bhadravati	Mile	0 2 0	120
10	Fixing the pipes and cagging joint	Each	2 0 0	5
11	Burnt stone slabs 6″ dressed and fixed	S.ft.	1 0 0	20
12	Providing one teak wood plug and iron rod with locking arrangement	L. S.	15 0 0	
13	Rough stone work new	C.yd.	2 8 0	60
14	Drilling holes in slabs	No.	1 0 0	2
15	Providing a jungle wood platform with slab support	L. S.		
16	Unforeseen items, clearing approach, etc.	,,		
	OTHER WORKS.			
1	Excavating check drain in hard soil and using sand for banking, etc.	C.yd.	0 4 0	700
2	Jungle clearing along bund and slopes	S.yd.	0 0 1½	3,112

D. A. HUKERI,
Executive Engineer.

CHITALDRUG DIVISION.

Abstract Notification dated 7th May 1940.

The attention of the public is invited to the notification for constructing Maternity Home at Hosdurga, published in the *Mysore Gazette*, dated 16th May 1940, Part VI on pages 1092-1095.

The last date of the tender is 3rd June 1940.

Notification dated 20th May 1940.

1. Sealed tenders will be received at the Office of the Executive Engineer, Chitaldrug Division, up to 2 P.M. on 12th June 1940, for restoring Heggere Hirekere, Register No. 31 of Hosadurga Taluk.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Chitaldrug Division, should be addressed to the Executive Engineer, Chitaldrug Division, in a sealed cover and superscribed as "Tender for restoring Heggere Hirekere—Register No. 31 of Hosadurga Taluk. The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a duplicate Treasury challan for having deposited Rs. 375 to "17 (a) P. W. Deposits" in the Treasury in cash or Government Promissory Notes or Mysore Government Bonds, duly endorsed at face value or market value, whichever is less, as earnest money. The earnest money of the successful tenderer will be retained as security deposit for the due fulfilment of the contract. Such a deposit in cash will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 12th June 1940 at 4 P.M. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental Schedule Contract Form for the due fulfilment of the contract, and for the execution of all items of work in accordance with the Bombay specifications (1931).

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Chitaldrug, on all working days, between 11 A.M. and 5 P.M. and the tender notification may be obtained from that officer on payment of four annas.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumsump amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made, the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department schedule of rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions or additions, at the discretion of the Executive Engineer or his representative. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

17. The works should be completed and handed over in a tidy condition to the Public Works Department by the end of May 1942, failing which the Executive Engineer may, at his discretion, levy a penalty of Rs. 20 per day, which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of disputes of any kind not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will however be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note.—(*a*) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labour required in setting out the works.
(2) Provide all necessary scaffolding, centering labour and appliances for hoisting.
(3) Provide mortar mills and sheds, to keep materials under cover and also for workmen.
(4) Arrange for protecting work during inclement weather.
(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.
(6) Supply all water required for work and workmen and shall provide temporary latrines and drains.
(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
(8) Provide arrangements for pumping and baling of water from excavations and foundations, wherever and whenever necessary with his own pumping apparatus including necessary leading drains, slump pits, etc.
(9) Afford facilities to any other parties employed upon the work by the P. W. D. so that their work may proceed during the progress of the contract, and give such persons the use of ordinary scaffolding and ladders.
(10) The contractor is responsible for all accidents to workmen, etc., on the work, and he must take precaution against all risk of accidents and, if necessary, provide for the same by insurance at the proper time.

Note.—(*b*) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

23. Chamundi Brand Cement should alone be used.

24. All lumpsum items of work will be measured and paid at lowest schedule rates.

Abstract of the estimate for restoring Heggere Hirekere Tank, Register No. 31, Hosadurga Taluk.

No.	Particulars of work	Quantity	Per	Rate	Rates tendered in	
					Figures	Words
				Rs. a. p.	Rs.	Rs.
1	Earthwork to bund including watering and consolidating up to 20′ lift and lead up to one furlong	14,700	C.yd.	0 4 6		
2	Riasing the earth got from excavating for waste weir body, wall including watering and consolidation with lead, etc., complete ..	83	,,	0 2 0		
3	Rough stone revetment including jelly filling and wedging and 2 to 3 miles lead ..	748	,,	1 8 0		
	(*a*) Gravel backing to revetment ..	249	,,	0 6 0		
4	Jungle clearing	44	Grade	2 8 0		
5	Cutting grip trenches	44	,,	5 0 0		
6	Providing and fixing index stone nicely dressed on a bed of slab or concrete ..	44	No.	1 4 0		
7	Providing and fixing grade stones as above with figures, etc., complete ..	44	,,	2 0 0		
8	Providing and fixing a gauge stone ..	1	,,	10 0 0		
9	Survey and constructive details stone ..	1	,,	15 0 0		
10	Removing and resetting disturbed revetment wherever required with new jelly	200	C.yd.	0 12 0		
11	Turfing the rear slope with watering, etc.	791.23	Sqr.	0 10 0		
12	Approach road ..		L.S.	..		
13	Unforseen charges		,,			

No.	Particulars of work	Quantity	Per	Rate	Rates tendered in	
					Figures	Words
				Rs. a. p.	Rs.	Rs.
	WASTE WEIR.					
1	Earth excavation for foundation of body wall and using the same for bund ..	83	C.yd.	0 3 0		
2	Size stone in surki mortar	443	C.ft.	0 4 6		
3	Burnt stone slabs of 4" thickness dressed and fixed in surki mortar ..	9	S.ft.	0 6 0		
4	Cement concrete coping of 1:2:4 with plastering	74	C.ft.	0 12 0		
5	Cement pointing 1:3 to the exposed portions	1.75	Sqr.	3 8 0		
6	Rough stone revetment new including lead of 2 to 3 miles	83	C.yd.	1 8 0		
7	Unforseen charges	..	L.S.	..		
	SLUICE.					
	Repairs to existing sluice	..	L.S.	..		

B. TIRUMALACHAR,
Executive Engineer.

MEDICAL DEPARTMENT.

THE GOVERNMENT AYURVEDIC AND UNANI COLLEGE, MYSORE.

Abstract Notification.

The attention of the public is invited to the notification, dated 8th May 1940, published on pages 1126-1133, Part VI of the *Mysore Gazette*, dated 16th May 1940, calling for tenders for the supply of drugs, articles of food, etc., to the Ayurvedic and Unani Hospitals, Mysore and Pharmacies attached thereto, for the year 1940-41.

M. RAMACHANDRAN,
Principal.

MINTO OPHTHALMIC HOSPITAL, BANGALORE.

Tender Notification dated 20th May 1940.

1. Notice is hereby given that sealed tenders in triplicate for supply of Furniture to the Minto Ophthalmic Hospital, Bangalore, will be received by the Secretary, Combined Hospitals, Bangalore at his office at the Victoria Hospital on Monday the 24th June 1940 at 11 A.M.
2. No tender will be received after the hour and date abovementioned.
3. No tender will be received unless accompanied by a Treasury receipt for Rs. 50 as earnest money.
4. Tenders to be superscribed tender for the supply of furniture to the Minto Ophthalmic Hospital, Bangalore.
5. Tenders will be opened by the Secretary at his office abovementioned.
6. The rate for each item must be specified in figures as well as in words and they must be for the particular kind of the articles. The value of each tender must be worked out according to the tender rates tendered and the total value must also be entered in word, in ink. Tenders not conforming to this rule will be rejected.
7. The Senior Surgeon does not bind himself to accept the lowest or any tender or to assign any reason for not accepting any tender.
8. The deposit of the successful tenderer will be retained and will be forfeited to Government if he fails to complete the contract in time.
9. No advance will be made to the Contractor.
10. The teakwood must be seasoned and of the best quality.
11. Samples can be seen at the Minto Hospital, Bangalore.
12. The articles must be supplied within 20 days from the date of the receipt of this order.